

GPS #: 7686

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: **6LA**

Page/Grid: 921/D-6

City / Location: Aliso Viejo

Scale Factor: 0.99996232

Ellipsoid Red. Factor: 0.99998457

Combination Factor: 0.99994690

Convergence Angle: -00 48 44.58127

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 57.92892	117 43 42.08869	2152797.781	6111344.319	322.358
2007.00	33 33 57.94604	117 43 42.10468	2152799.53	6111342.99	

References: MM 650/29-30, RSB 150/36-50

Description:

**FD PUNCHED SPIKE AND 1 1/2" BRASS WASHER,
STAMPED "LS 4541", DOWN 0.02' IN A.C., STATION IS
LOCATED AT CENTERLINE INTER OF LAGUNA HILLS
DR. AND LIBERTY.**

