

GPS #: 7692

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 921/F-4

City / Location: Aliso Viejo

Scale Factor: 0.99996330

Ellipsoid Red. Factor: 0.99999468

Combination Factor: 0.99995798

Convergence Angle: -00 48 16.45949

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 46.59560	117 42 50.91328	2157655.301	6115743.254	111.132
2007.00	33 34 46.61280	117 42 50.92945	2157657.06	6115741.91	

References: MM 667/41-45, RSB 150/36-50

Description:

FD PUNCHED SPIKE AND 1 1/2" BRASS WASHER, STAMPED "LS 6039", FLUSH IN A.C., STATION IS LOCATED AT CENTERLINE INTER OF CEDARBROOK AND PARK AVE.

