

GPS #: 7703

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 921/H-2

City / Location: Laguna Hills

Scale Factor: 0.99996493

Ellipsoid Red. Factor: 0.99998706

Combination Factor: 0.99995199

Convergence Angle: -00 47 48.23791

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 01.73860	117 41 59.55627	2165189.154	6120193.429	270.439
2007.00	33 36 01.75570	117 41 59.57251	2165190.90	6120192.08	

References: A/7-8 1125, RSB 150/36-50

Description:

FD PUNCHED SPIKE AND WASHER, STAMPED "LS 2921", FLUSH IN A.C., STATION IS LOCATED AT CENTERLINE B.C. ALONG BECKENHAM ST., 150'+/- E'LY OF SUNSET PLACE.

