

GPS #: **7710R2**

Date Destroyed:

Date Revised: 7/10/2016

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 892/B-6

City / Location: Mission Viejo

Scale Factor: 0.99996630

Ellipsoid Red. Factor: 0.99997476

Combination Factor: 0.99994106

Convergence Angle: -00 46 40.88706

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 01.16726	117 39 56.99267	2171053.092	6130640.855	
2007.00	33 37 01.18417	117 39 57.00850	2171054.82	6130639.54	

References: MM 272/1-5, RSB 150/36-50, CR 2001-0871, CR 2015-1997, CR 2016-0295

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 5411"
FLUSH PER CR 2016-0295 IN LIEU OF LEAD AND
TACK WITH OCS BRASS TAG STAMPED "7710R1 5-
01" FLUSH IN POR-ROK, IN LIEU OF PUNCHED BOLT
SPIKE WITH 1 1/4" WASHER. MONUMENT WAS
RESET PER CORNER RECORD # 2001-871. STATION
IS LOCATED AT CENTERLINE INTER OF VALPARISO
DR. AND SALVADOR DR.