

GPS #: **7711R1**

Date Destroyed:

Date Revised: 6/4/2001

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 892/B-7

City / Location: Mission Viejo

Scale Factor: 0.99996565

Ellipsoid Red. Factor: 0.99998235

Combination Factor: 0.99994801

Convergence Angle: -00 46 45.25938

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 33.43075	117 40 04.94934	2168258.931	6129929.915	
2007.00	33 36 33.44768	117 40 04.96516	2168260.66	6129928.60	

References: MM 252/48-50, RSB 150/36-50, CR 2001-0872

Description:

FD PUNCHED SPIKE AND 1 1/4" OCS BRASS WASHER STAMPED "7711R1 4-01" FLUSH, IN LIEU OF PUNCHED BOLT SPIKE WITH TIN. MONUMENT WAS RESET PER CORNER RECORD # 2001-872. STATION IS LOCATED AT CENTERLINE INTER OF CARRILLO DR. AND SINFOROSA DR.

