

**GPS #:** 7717

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 892/D-4

City / Location: Mission Viejo

Scale Factor: 0.99996786

Ellipsoid Red. Factor: 0.99996366

Combination Factor: 0.99993151

Convergence Angle: -00 46 16.54362

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 38 04.28706 | 117 39 12.69302 | 2177381.941   | 6134472.695  | 759.526               |
| 2007.00          | 33 38 04.30389 | 117 39 12.70885 | 2177383.66    | 6134471.38   |                       |

References: MM 380/40-43, RSB 150/36-50

**Description:**

FD 2" I.P. WITH TACK AND TAG IN CONC., STAMPED "RCE 14749", DOWN 1.43' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE B.C. ALONG ALLARIZ ST., 100'+/- NE OF ORELLANA ST.

