

GPS #: **7723**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 892/A-4

City / Location: Lake Forest

Scale Factor: 0.99996775

Ellipsoid Red. Factor: 0.99998203

Combination Factor: 0.99994978

Convergence Angle: -00 47 05.85369

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 59.94382	117 40 42.42639	2177046.004	6126880.394	375.573
2007.00	33 37 59.96072	117 40 42.44222	2177047.73	6126879.08	

References: MM 456/37-40, RSB 150/36-50

Description:

FD PUNCHED 2" BRASS DISK IN CONC. , STAMPED "LS 2921", DOWN 1.61' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF BROOKHAVEN ST. AND GLENHURST ST.

