

GPS #: 7728

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 891/J-7

City / Location: Mission Viejo

Scale Factor: 0.99996557

Ellipsoid Red. Factor: 0.99998641

Combination Factor: 0.99995199

Convergence Angle: -00 47 28.86183

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 30.13561	117 41 24.29613	2168017.869	6123215.208	283.956
2007.00	33 36 30.15265	117 41 24.31233	2168019.61	6123213.86	

References: MM 383/29-35, RSB 150/36-50

Description:

FD PUNCHED SPIKE WITH 1 1/2" ALUMINUM WASHER, STAMPED "LS 3419", DOWN 0.13' IN A.C., STATION IS LOCATED AT THE CENTERLINE INTER OF CHARLINDA DR. AND ARGONAUT DR.

