

GPS #: **7732**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 892/A-6

City / Location: Mission Viejo

Scale Factor: 0.99996654

Ellipsoid Red. Factor: 0.99998074

Combination Factor: 0.99994728

Convergence Angle: -00 47 03.74851

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 10.83347	117 40 38.59544	2172078.015	6127136.322	402.401
2007.00	33 37 10.85025	117 40 38.61135	2172079.73	6127135.00	

References: PMB 271/21-22, RSB 150/36-50

Description:

FD PUNCHED BOLT SPIKE WITH 1 1/4" BRASS WASHER, STAMPED "RCE 14749", FLUSH IN A.C., STATION IS LOCATED AT CENTERLINE B.C. ALONG PALA ST., 198.14' SOUTH FROM ITS CENTERLINE INTER WITH ALAMBRE ST.

