

GPS #: 7741

Date Destroyed:

Date Revised: 7/11/2011

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 892/D-3

City / Location: Mission Viejo

Scale Factor: 0.99996838

Ellipsoid Red. Factor: 0.99996272

Combination Factor: 0.99993110

Convergence Angle: -00 46 04.92680

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 24.86299	117 38 51.55298	2179437.541	6136287.809	779.099
2007.00	33 38 24.87982	117 38 51.56875	2179439.26	6136286.50	

References: MM 403/12-15, RSB 150/36-50, CR 2011-0158, CR 2011-0830

Description:

FD 2" I.P. WITH TACK AND TAG IN CONC., STAMPED "RCE 14749", DOWN 1.41' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE B.C. ALONG ALARCON ST., 129.10' NE FROM ITS CENTERLINE INTER WITH MONTELLANO ST.

