

GPS #: **7744**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 892/E-1

City / Location: Mission Viejo

Scale Factor: 0.99996954

Ellipsoid Red. Factor: 0.99996558

Combination Factor: 0.99993511

Convergence Angle: -00 45 56.49483

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 08.56845	117 38 36.20867	2183837.502	6137644.011	719.411
2007.00	33 39 08.58516	117 38 36.22434	2183839.21	6137642.71	

References: MM 549/27-29, RSB 150/36-50

Description:

FD 2" I.P. WITH TACK AND TAG IN CONC., STAMPED "LS ____", DOWN 1.43' IN WELL MONUMENT. ACCEPTED AS TACK AND TAG STAMPED "LS 3906" IN CONC. PER MM 549/27-29. STATION IS LOCATED AT CENTERLINE B.C. ALONG BRISTLECONE ST., 738.82' S'LY FROM ITS CENTERLINE INTER WITH MOUNTAIN ST.

