

GPS #: **7753**

Date Destroyed:

Date Revised: 1/15/2013

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 920/A-6

City / Location: Laguna Beach

Scale Factor: 0.99996245

Ellipsoid Red. Factor: 1.00000009

Combination Factor: 0.99996254

Convergence Angle: -00 52 09.39763

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 04.50475	117 49 54.80898	2153925.190	6079819.448	-1.814
2007.00	33 34 04.52157	117 49 54.82558	2153926.91	6079818.07	

References: RSB 133/34-35, RSB 150/10-23, CR 2011-1902

Description:

FD PUNCHED SPIKE AND 1" STEEL STATE OF CALIFORNIA DIVISION OF HWY.S WASHER, FLUSH IN A.C., STATION IS LOCATED AT CENTERLINE E.C. ALONG PACIFIC COAST HWY., 0.4+/- MILE NW'LY OF EL MORRO SCHOOL ENTRANCE ON E'LY SIDE OF HWY. AND 0.2+/- MILE NW'LY OF ENTRANCE TO REEF POINT PARKING AREA.

