

GPS #: **7756**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 971/D-2

City / Location: Laguna Beach

Scale Factor: 0.99995801

Ellipsoid Red. Factor: 0.99999660

Combination Factor: 0.99995461

Convergence Angle: -00 48 59.47676

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 29 36.77451	117 44 09.19517	2126436.479	6108674.725	71.043
2007.00	33 29 36.79134	117 44 09.21158	2126438.20	6108673.36	

References: RSB 150/36-50

Description:

FD 3 1/4" ALUMINUM, CITY OF LAGUNA NIGUEL, GPS CONTROL STATION DISK, STAMPED "1301", UP 0.05' IN DIRT. STATION IS LOCATED 15'+/- NORTH OF THE EDGE OF PAVEMENT ALONG THE NORTHBOUND PACIFIC COAST HWY., 0.65'+/- MILE N'LY OF CROWN VALLEY PKWY.

