

GPS #: 7762R1

Date Destroyed:

Date Revised: 5/27/2014

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 891/D-7

City / Location: Laguna Hills

Scale Factor: 0.99996563

Ellipsoid Red. Factor: 0.99998244

Combination Factor: 0.99994807

Convergence Angle: -00 48 52.48313

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 32.69995	117 43 56.46832	2168457.402	6110350.089	
2007.00	33 36 32.71705	117 43 56.48455	2168459.15	6110348.74	

References: RSB 150/36-50, CR 2002-2069, CR 2010-1760, CR 2013-3246, CR 2014-0419

Description:

FD PK NAIL AND WASHER STAMPED "LS 6970".
MONUMENT WAS RESET PER CORNER RECORD
#2002-2069B IN LIEU OF PUNCHED SPIKE AND 1 1/2"
STEEL WASHER, (NO STAMPING) DOWN 0.10' IN A.C.
SURFACE . STATION IS LOCATED AT APPARENT
CENTERLINE INTER OF EL TORO RD. AND CALLE
SONORA.

