

**GPS #:** **7764**

**Date Destroyed:** **9/1/2012**

**Date Revised:** **8/28/2006**

**Benchmark Designation:**

**OCS Index Map:** **6LA**

**Page/Grid:** **891/A-5**

**City / Location:** **Irvine**

**Scale Factor:** **0.99996705**

**Ellipsoid Red. Factor:** **0.99998602**

**Combination Factor:** **0.99995307**

**Convergence Angle:** **-00 49 42.65533**

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 37 31.79296 | 117 45 27.77058 | 2174540.536   | 6102715.363  | 292.073               |
| 2007.00          | 33 37 31.80983 | 117 45 27.78710 | 2174542.26    | 6102713.99   |                       |

**References:** CALTRANS AOR133A 0106, RSB 150/36-50, RS 2001-1064

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: RECOVERED 8/2001PUNCHED SPIKE AND 1-1/4" WASHER (ILLEGIBLE), DOWN 0.1'. ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND 1 1/4" STEEL WASHER, FLUSH IN A.C., STATION IS LOCATED AT CENTERLINE POINT OF TANGENCY ALONG LAGUNA CANYON RD., 1.25+/- MILES S'LY OF LAGUNA FREEWAY AND OLD LAGUNA CANYON RD. INTER, AND 3.0+/- MILES N'LY FROM ITS INTER WITH EL TORO RD.