

GPS #: **7769**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 920/J-5

City / Location: Laguna Beach

Scale Factor: 0.99996319

Ellipsoid Red. Factor: 0.99999524

Combination Factor: 0.99995842

Convergence Angle: -00 49 51.78660

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 41.03209	117 45 44.38745	2157302.493	6101060.058	99.567
2007.00	33 34 41.04898	117 45 44.40369	2157304.22	6101058.71	

References: CALTRANS AOR133A 0092, RSB 150/36-50

Description:

FD PUNCHED SPIKE AND 1 1/2" BRASS CALTRANS WASHER, FLUSH IN A.C., STATION IS LOCATED AT POINT OF TANGENCY ALONG CENTERLINE OF LAGUNA CANYON RD. 0.25+/- MILE S'LY FROM ITS INTER WITH EL TORO RD.

