

GPS #: 7770

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 950/H-3

City / Location: Laguna Beach

Scale Factor: 0.99996076

Ellipsoid Red. Factor: 0.99999516

Combination Factor: 0.99995592

Convergence Angle: -00 50 14.16601

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 33.69278	117 46 25.11302	2144482.925	6097426.755	101.142
2007.00	33 32 33.70955	117 46 25.12944	2144484.64	6097425.39	

References: RSB 150/36-50

Description:

FD PUNCHED SPIKE AND 1 1/2" WASHER, STAMPED "LS 4453", FLUSH IN A.C., STATION IS LOCATED 25'+/- W'LY OF APPARENT CENTERLINE INTER OF PARK AVE. AND SKYLINE TERRACE.

