

**GPS #:** **7772**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 951/B-5

City / Location: Laguna Beach

Scale Factor: 0.99995970

Ellipsoid Red. Factor: 0.99997019

Combination Factor: 0.99992989

Convergence Angle: -00 49 26.30763

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 30.86627	117 44 58.02141	2138026.429	6104706.038	622.945
2007.00	33 31 30.88329	117 44 58.03762	2138028.17	6104704.69	

References: RSB 150/36-50, RSB 74/49.

**Description:**

FD 4" CONC. FILLED I.P. WITH NAIL AND TAG, STAMPED "LS 2609", UP 0.8' IN DIRT. TO REACH THE STATION FROM THE INTER OF BALBOA AVE. AND CORTEZ AVE., HIKE 500'+/- E'LY ALONG A PAVED FOOT TRAIL THROUGH THE PARK AND STOP BEFORE REACHING EXERCISE AREA. PROCEED SE'LY ALONG DIRT TRAIL, THEN E'LY TO A FENCE AND POWER LINE. CONTINUE S'LY TO STATION AT FENCE CORNER.

