

GPS #: **7773**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 921/A-4

City / Location: Laguna Beach

Scale Factor: 0.99996343

Ellipsoid Red. Factor: 0.99999413

Combination Factor: 0.99995756

Convergence Angle: -00 49 50.38145

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 52.87067	117 45 41.83042	2158495.847	6101293.723	122.706
2007.00	33 34 52.88752	117 45 41.84657	2158497.57	6101292.38	

References: RSB 150/36-50

Description:

FD SPIKE AND CALTRANS WASHER, FLUSH IN ROCK OUTCROPPING. TO REACH THE STATION FROM THE INTER OF LAGUNA CANYON RD. AND EL TORO RD., PROCEED S'LY ALONG LAGUNA CANYON RD. 0.1 MILE TO THE STATION LOCATED 25'+/- WEST FROM EDGE OF PAVEMENT AND 15'+/- HIGHER THAN RD. SURFACE.

