

GPS #: **7774**

Date Destroyed:

Date Revised: 6/4/2001

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 920/J-6

City / Location: Laguna Beach

Scale Factor: 0.99996278

Ellipsoid Red. Factor: 0.99999670

Combination Factor: 0.99995947

Convergence Angle: -00 49 53.25978

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 20.89446	117 45 47.06834	2155270.535	6100803.730	69.048
2007.00	33 34 20.91133	117 45 47.08458	2155272.26	6100802.38	

References: CALTRANS AOR133A 0090, RSB 150/36-50

Description:

FD PUNCHED BOLT SPIKE WITH CALTRANS WASHER, FLUSH IN A.C., STATION IS LOCATED AT CENTERLINE E.C. (CALTRANS STATION 143+32.10) ALONG LAGUNA CANYON RD., 280'+/- N'LY OF THE ENTRANCE TO G.T.E. SERVICE YARD AND 0.2 MILE NORTH FROM ITS INTER WITH STAN OAK DR.

