

**GPS #:** **7777**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 950/H-1

City / Location: Laguna Beach

Scale Factor: 0.99996168

Ellipsoid Red. Factor: 1.00000076

Combination Factor: 0.99996244

Convergence Angle: -00 50 15.14373

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 24.34229	117 46 26.89225	2149604.077	6097351.011	-15.951
2007.00	33 33 24.35903	117 46 26.90851	2149605.79	6097349.66	

References: CALTRANS AOR133A 0080, RSB 150/36-50

**Description:**

FD PUNCHED BOLT SPIKE AND CALTRANS WASHER, DOWN 0.02', IN A.C., STATION IS LOCATED AT CENTERLINE E.C. (CALTRANS STATION 64+16.46) ALONG LAGUNA CANYON RD., 0.15 MILE NORTH FROM ITS INTER WITH CANYON ACRES DR.

