

GPS #: 7801

Date Destroyed:

Date Revised: 5/15/2002

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 830/F-7

City / Location: Irvine

Scale Factor: 0.99997636

Ellipsoid Red. Factor: 1.00000112

Combination Factor: 0.99997748

Convergence Angle: -00 50 40.59237

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



| Epoch Adjustment | Latitude | Longitude | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35 | 33 42 59.18591 | 117 47 13.20314 | 2207759.987 | 6094288.844 | -23.350 |
| 2007.00 | 33 42 59.20215 | 117 47 13.21969 | 2207761.65 | 6094287.47 | |

References: CR 2002-0825

Description:

FOUND PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "07-01 GPS 7801", FLUSH. MONUMENT IS LOCATED IN THE SOUTHERLY PORTION OF A "T" INTERSECTION OF COMMERCE, SOUTHERLY FROM EL CAMINO REAL.

