

**GPS #:** 9000

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 1023/D-3

City / Location: San Diego Co.

Scale Factor: 0.99995451

Ellipsoid Red. Factor: 1.00000214

Combination Factor: 0.99995665

Convergence Angle: -00 43 59.97267

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 22 59.30376 | 117 35 04.16422 | 2085641.304   | 6154313.361  | -44.616               |
| 2007.00          | 33 22 59.32055 | 117 35 04.17981 | 2085643.02    | 6154312.06   |                       |

References: NO REFERENCE

**Description:**

FD 4" I.P. WITH 3 1/4" U.S.C. & G.S. BRASS DISK STAMPED "MEDIO 1884", UP 0.9' FROM DIRT SURFACE, LOCATED 0.2 +/- MILE SW'LY FROM THE BASOLINE RD. OVERCROSSING THE 5 FREEWAY, ALONG THE BLUFF OVERLOOKING THE OCEAN, 150'+/- NW'LY FROM THE LIFEGUARD TOWER, IN SAN DIEGO COUNTY.

