

GPS #: 9001

Date Destroyed: 7/25/2000

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 993/A-1

City / Location: San Clemente

Scale Factor: 0.99995620

Ellipsoid Red. Factor: 0.99999477

Combination Factor: 0.99995098

Convergence Angle: -00 44 49.47415

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 01.68639	117 36 34.24591	2110236.534	6146995.035	109.252
2007.00	33 27 01.70330	117 36 34.26135	2110238.26	6146993.75	

References: RSB 151/1-11

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2 1/2" BRASS O.C.S. DISK STAMPED "O.C.S. CREAMERS 9001" FLUSH IN A.C. SERVICE RD., LOCATED 100'+/- NE'LY OF S.D.G. & E. BUILDING, 200'+/- N'LY FROM THE INTER OF AVENIDA PICO AND CALLE DE AMANECER.