

GPS #: 9009

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 922/D-7

City / Location: Mission Viejo

Scale Factor: 0.99996209

Ellipsoid Red. Factor: 0.99998425

Combination Factor: 0.99994634

Convergence Angle: -00 46 19.78660

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 45.75561	117 39 18.59453	2151259.152	6133621.604	329.077
2007.00	33 33 45.77252	117 39 18.61056	2151260.88	6133620.27	

References: RSB 150/36-50

Description:

FD 2 1/2" O.C.S. BRASS DISK STAMPED "LEMONHEAD OCS 9009" FLUSH WITH CONC. SURFACE OF ELECTRICAL VAULT PAD, LOCATED S'LY FROM THE CENTERLINE OF CROWN VALLEY PKWY. ON TOP OF A ELECTRICAL VAULT PAD, 0.15 MILE E'LY FROM ITS INTER WITH MARGUERITE PKWY.

