

GPS #: 9010

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 992/C-1

City / Location: Dana Point

Scale Factor: 0.99995632

Ellipsoid Red. Factor: 1.00000467

Combination Factor: 0.99996099

Convergence Angle: -00 46 41.22844

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 13.34363	117 39 57.61392	2111644.015	6129781.444	-97.667
2007.00	33 27 13.36061	117 39 57.62971	2111645.75	6129780.13	

References: RSB 151/1-11

Description:

SET 2" O.C.S. BRASS CAP STAMPED "PEEWEE 8
OCS 9010" CEMENTED FLUSH IN SIDEWALK,
LOCATED 65'+/- NW'LY FROM THE SE'LY END OF THE
SAN JUAN CAPISTRANO BEACH PARKING LOT, ON
THE SIDEWALK OF A SMALL ISLAND NOSE.

