

GPS #: BIKE

Date Destroyed: **7/25/2000**
 Date Revised: **8/23/1996**
 Benchmark Designation:
 OCS Index Map: **6LA**
 Page/Grid: **972/C-3**
 City / Location: **San Juan Capistrano**

Scale Factor: **0.99995786**
 Ellipsoid Red. Factor: **1.00000195**
 Combination Factor: **0.99995981**
 Convergence Angle: **-00 46 40.65541**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 29 25.71849	117 39 56.57112	2125021.412	6130051.452	-40.837
2007.00	33 29 25.73541	117 39 56.58725	2125023.14	6130050.11	

References: OCS FILE # P88-2

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD P.K. NAIL AND OCS BRASS TAG STAMPED "BIKE" FLUSH IN A.C. BIKE TRAIL. LOCATED FROM THE INTER OF DEL OBISBO ST. AND PASEO ADELANTO, PROCEED S'LY ALONG PASEO ADELANTO 0.3 MILES TO THE BIKE TRAIL ENTRANCE ON RIGHT. PROCEED ON A.C. BIKE TRAIL AND CONTINUE S'LY ALONG EAST LEVEE OF SAN JUAN CREEK CHANNEL 0.2 MILES TO SAID MONUMENT LOCATED AT THE APPARENT INTER OF THE CENTER OF THE BIKE TRAIL AND THE CENTER OF THE STEEL PEDESTRIAN BRIDGE, 6' EAST OF A 4" DIA., 4' HIGH GUARD POST.