

GPS #: **LANA**

Date Destroyed:
Date Revised: 8/23/1996
Benchmark Designation:
OCS Index Map: 6LA
Page/Grid: 972/A-4
City / Location: San Juan Capistrano

Scale Factor: 0.99995739
Ellipsoid Red. Factor: 1.00000305
Combination Factor: 0.99996044
Convergence Angle: -00 47 05.68684

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 28 48.58712	117 40 42.12276	2121321.303	6126142.631	-63.756
2007.00	33 28 48.60393	117 40 42.13888	2121323.02	6126141.29	

References: OCS FILE # F90-16J

Description:

FD PUNCHED SPIKE AND 1 1/4" BRASS OCS TAG STAMPED "LANA 6/90" FLUSH IN A.C. BIKE TRAIL ON EAST SIDE OF SAN JUAN CREEK, 1.7' W'LY FROM THE CENTER OF AN A.C. BERM, 350' +/- S'LY FROM THE APPARENT BC OF RIGHT HAND CURVE IN CHANNEL, AND 450' +/- N'LY FROM THE PROD OF CALLE JARDIN.

