

GPS #: **P252**

Date Destroyed: **7/25/2000**
Date Revised:
Benchmark Designation:
OCS Index Map: 5LA
Page/Grid: 889/D-6
City / Location: Newport Beach

Scale Factor: 0.99996701
Ellipsoid Red. Factor: 1.00000500
Combination Factor: 0.99997208
Convergence Angle: -00 53 54.63234

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 30.58036	117 53 06.31279	2175002.326	6063943.937	-104.035
2007.00	33 37 30.59669	117 53 06.32986	2175004.00	6063942.52	

References: OCS SURVEY FILE # P93-1N

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED CUT-SPIKE AND 1 1/4" OCS BRASS TAG, STAMPED "GPS P252", FLUSH IN ASPHALT. LOCATED SW FROM THE INTER OF SAN JOAQUIN HILLS RD. AND JAMBOREE RD.; SET ALONG BACK BAY DR., APPROX. 150' SOUTH OF THE INTER OF BACK BAY DR. AND SAN JOAQUIN HILLS RD.