

**GPS #:** **P253**

**Date Destroyed:** **7/25/2000**

**Date Revised:**

**Benchmark Designation:**

**OCS Index Map:** **5LA**

**Page/Grid:** **889/D-5**

**City / Location:** **Newport Beach**

**Scale Factor:** **0.99996762**

**Ellipsoid Red. Factor:** **1.00000500**

**Combination Factor:** **0.99997271**

**Convergence Angle:** **-00 53 54.06499**

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 55.06369	117 53 05.28034	2177475.401	6064070.030	-104.531
2007.00	33 37 55.08008	117 53 05.29734	2177477.08	6064068.62	

**References:** **OCS SURVEY FILE # P93-1N**

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED CUT-SPIKE AND 1 1/4" OCS BRASS TAG, STAMPED "GPS P253", FLUSH IN ASPHALT. LOCATED NW FROM THE INTER OF JAMBOREE RD. AND SAN JOAQUIN HILLS RD.; SET ALONG BACK BAY DR., APPROX. 0.6 MILE NORTH FROM THE INTER OF SAN JOAQUIN HILLS RD. AND BACK BAY DR.