

GPS #: **P255**

Date Destroyed: **7/25/2000**

Date Revised:

Benchmark Designation:

OCS Index Map: **5LA**

Page/Grid: **889/D-4**

City / Location: **Newport Beach**

Scale Factor: **0.99996782**

Ellipsoid Red. Factor: **1.00000500**

Combination Factor: **0.99997292**

Convergence Angle: **-00 53 54.82462**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 03.04769	117 53 06.66270	2178284.149	6063965.818	-104.760
2007.00	33 38 03.06399	117 53 06.67967	2178285.82	6063964.41	

References: **OCS SURVEY FILE # P93-1N**

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED CUT-SPIKE AND 1 1/4" OCS BRASS TAG, STAMPED "GPS P255", FLUSH IN ASPHALT. LOCATED NW OF THE INTER OF SAN JOAQUIN HILLS RD. AND JAMBOREE RD.; SET ALONG BACK BAY DR., APPROX. 0.8 MILE NORTH FROM THE INTER OF SAN JOAQUIN HILLS RD. AND BACK BAY DR.