

**GPS #:** **P258**

**Date Destroyed:** **7/25/2000**  
**Date Revised:**  
**Benchmark Designation:**  
**OCS Index Map:** 5LA  
**Page/Grid:** 889/D-4  
**City / Location:** Newport Beach

**Scale Factor:** 0.99996823  
**Ellipsoid Red. Factor:** 1.00000510  
**Combination Factor:** 0.99997341  
**Convergence Angle:** -00 53 57.52692

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 19.22596	117 53 11.58029	2179925.755	6063575.750	-106.342
2007.00	33 38 19.24230	117 53 11.59705	2179927.43	6063574.36	

**References:** OCS SURVEY FILE # P93-1N

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED CUT-SPIKE AND 1 1/4" OCS BRASS TAG, STAMPED "GPS P258", FLUSH IN ASPHALT. LOCATED NW OF THE INTER OF SAN JOAQUIN HILLS RD. AND JAMBOREE RD.; SET ALONG BACK BAY DR., APPROX. 1.1 MILES NORTH FROM THE INTER OF SAN JOAQUIN HILLS RD. AND BACK BAY DR.