

**GPS #:** **P260**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/D-3

City / Location: Newport Beach

Scale Factor: 0.99996843

Ellipsoid Red. Factor: 1.00000140

Combination Factor: 0.99996985

Convergence Angle: -00 53 51.57703

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 26.96254	117 53 00.75280	2180693.312	6064503.313	-27.848
2007.00	33 38 26.97901	117 53 00.76959	2180695.00	6064501.92	

References: OCS SURVEY FILE # P93-1N

**Description:**

FD 1 1/4" OCS BRASS TAG AND NAIL, STAMPED "GPS P260", FLUSH IN CONC. SURFACE OF A SEWER MANHOLE VAULT. LOCATED NW OF THE INTER OF EASTBLUFF DR. AND JAMBOREE RD.; SET OFF VISTA ENTRADA ALONG A GREENBELT OVERLOOKING NEWPORT BAY, ON TOP OF AN 8' X 8' SQUARE SEWER VAULT.

