

GPS #: **P262**

Date Destroyed: **7/25/2000**

Date Revised:

Benchmark Designation:

OCS Index Map: **5LA**

Page/Grid: **889/D-3**

City / Location: **Newport Beach**

Scale Factor: **0.99996869**

Ellipsoid Red. Factor: **1.00000510**

Combination Factor: **0.99997381**

Convergence Angle: **-00 53 49.15281**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 36.90625	117 52 56.34127	2181692.451	6064891.971	-105.184
2007.00	33 38 36.92274	117 52 56.35805	2181694.14	6064890.58	

References: **OCS SURVEY FILE # P93-1N**

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED CUT-SPIKE AND 1 1/4" OCS BRASS TAG, STAMPED "GPS P262", FLUSH IN ASPHALT. LOCATED NW OF THE INTER OF SAN JOAQUIN HILLS RD. AND JAMBOREE RD.; SET ALONG BACK BAY DR., APPROX. 1.55 MILES NORTH FROM THE INTER OF SAN JOAQUIN HILLS RD. AND BACK BAY DR.