

GPS #: **P264**

Date Destroyed: **1/1/1998**

Date Revised:

Benchmark Designation:

OCS Index Map: **5LA**

Page/Grid: **889/E-3**

City / Location: **Newport Beach**

Scale Factor: **0.99996898**

Ellipsoid Red. Factor: **1.00000520**

Combination Factor: **0.99997419**

Convergence Angle: **-00 53 41.36543**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 48.03728	117 52 42.16997	2182798.697	6066107.460	-106.968
2007.00	33 38 48.05370	117 52 42.18672	2182800.38	6066106.07	

References: **OCS SURVEY FILE # P93-1N**

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED CUT-SPIKE AND 1 1/4" OCS BRASS TAG, STAMPED "GPS P264", FLUSH IN ASPHALT. LOCATED IN A N'LY DIRECTION FROM THE INTER OF SAN JOAQUIN HILLS RD. AND JAMBOREE RD.; SET ALONG BACK BAY DR., APPROX. 0.5 MILE WEST FROM THE INTER OF BACK BAY DR. AND EASTBLUFF DR.