

GPS #: **P267**

Date Destroyed: **7/25/2000**

Date Revised:

Benchmark Designation:

OCS Index Map: **5LA**

Page/Grid: **889/E-3**

City / Location: **Newport Beach**

Scale Factor: **0.99996886**

Ellipsoid Red. Factor: **1.00000470**

Combination Factor: **0.99997356**

Convergence Angle: **-00 53 30.40697**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 43.38966	117 52 22.22799	2182302.693	6067785.809	-96.535
2007.00	33 38 43.40603	117 52 22.24485	2182304.37	6067784.41	

References: **OCS SURVEY FILE # P93-1N**

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED CUT-SPIKE AND 1 1/4" OCS BRASS TAG, STAMPED "GPS P267", FLUSH IN ASPHALT. LOCATED IN A N'LY DIRECTION FROM THE INTER OF SAN JOAQUIN HILLS RD. AND JAMBOREE RD.; SET ALONG BACK BAY DR., APPROX. 0.15 MILE WEST FROM THE INTER OF BACK BAY DR. AND EASTBLUFF DR.