

GPS #: **P276**

Date Destroyed: **7/25/2000**

Date Revised:

Benchmark Designation:

OCS Index Map: **5LA**

Page/Grid: **889/E-2**

City / Location: **Newport Beach**

Scale Factor: **0.99996924**

Ellipsoid Red. Factor: **1.00000520**

Combination Factor: **0.99997448**

Convergence Angle: **-00 53 38.11778**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 57.50616	117 52 36.25997	2183747.891	6066621.954	-107.930
2007.00	33 38 57.52264	117 52 36.27677	2183749.58	6066620.56	

References: **OCS SURVEY FILE # P93-1N**

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 1" I.P. WITH CAP AND 1 1/4" OCS BRASS TAG AND TACK, STAMPED "GPS P276". LOCATED SW OF THE INTER OF JAMBOREE RD. AND BAYVIEW WAY; SET OFF A DIRT PATH SOUTH OF A BIKE TRAIL, PAST A POST MARKED 'BOUNDARY ECOLOGICAL PRESERVE'.