

GPS #: **P282**

Date Destroyed:

Date Revised: 3/11/2004

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/F-2

City / Location: Newport Beach

Scale Factor: 0.99996959

Ellipsoid Red. Factor: 1.00000410

Combination Factor: 0.99997379

Convergence Angle: -00 53 22.80837

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 10.73498	117 52 08.40024	2185048.236	6068997.581	-85.981
2007.00	33 39 10.75142	117 52 08.41700	2185049.92	6068996.19	

References: OCS SURVEY FILE # P93-1N

Description:

FD TRIANGULAR WELL MONUMENT WITH PUNCHED 2" BRASS DISK, DOWN 0.9'. LOCATED IN A W'LY DIRECTION FROM THE INTER OF JAMBOREE RD. AND BAYVIEW WAY; SET AT THE CENTERLINE INTER OF BAYVIEW WAY AND BAYVIEW PLACE.

