

**GPS #:** **R103**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 826/G-1

City / Location: Seal Beach

Scale Factor: 0.99998230

Ellipsoid Red. Factor: 1.00000530

Combination Factor: 0.99998768

Convergence Angle: -01 00 44.62961

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 52.32642	118 05 32.41682	2226763.267	6001758.707	-111.374
2007.00	33 45 52.34282	118 05 32.43395	2226764.95	6001757.29	

References: RS 92-1117

**Description:**

FD 6" CONC. POST AND 5" IRON CAP WITH RAISED NUMBER '3' AND BORDER ENCASED IN A 12" DIA. PIPE AND CONC. COLLAR, UP 0.3'. LOCATED WEST FROM THE INTER OF WESTMINSTER AVE. AND SEAL BEACH BLVD.; SET ALONG THE W'LY LEVEE, 1' EAST OF AN ANGLE POINT IN AN 8' HIGH CHAINLINK FENCE.

