

GPS #: **R104**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 796/F-6

City / Location: Seal Beach

Scale Factor: 0.99998389

Ellipsoid Red. Factor: 1.00000510

Combination Factor: 0.99998904

Convergence Angle: -01 00 58.03749

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 35.48539	118 05 56.81617	2231161.673	5999776.497	-106.427
2007.00	33 46 35.50172	118 05 56.83343	2231163.35	5999775.07	

References: RS 92-1117

Description:

FD 2" BRASS COUNTY ENGINEER R.E. 5869 DISK STAMPED "LA CO. / O CO. STA #6", DOWN 1.5'. LOCATED SE FROM THE INTER OF STUDEBAKER RD. AND 9TH ST.; SET EAST OF THE BACK OF WALK ON STEVELY WAY, SOUTH OF THE INTER OF STEVELY WAY AND KALLIN WAY, NEAR COLLEGE PARK.

