

GPS #: **R108**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 767/A-7

City / Location: Cypress

Scale Factor: 0.99998997

Ellipsoid Red. Factor: 1.00000430

Combination Factor: 0.99999428

Convergence Angle: -00 59 47.10389

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 10.68510	118 03 47.73277	2246656.096	6010943.906	-88.730
2007.00	33 49 10.70110	118 03 47.75037	2246657.74	6010942.45	

References: RS 92-1117

Description:

FD 2 1/2" LA COUNTY ENGINEER MONUMENT RE 5869 BRASS DISK STAMPED "LA CO. STA #10 OR. CO.", IN CONC., DOWN 1.9'. LOCATE NE OF THE INTER OF BALL RD. AND BLOOMFIELD ST.; SET IN WEST LN. OF BLOOMFIELD ST., 12' EAST OF THE W'LY CURB, APPROX. 370' SOUTH OF LITTLEFIELD ST.

