

**GPS #:** **R113**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 767/A-4

City / Location: La Palma

Scale Factor: 0.99999400

Ellipsoid Red. Factor: 1.00000330

Combination Factor: 0.99999733

Convergence Angle: -00 59 38.76416

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 50 46.29030	118 03 32.55630	2256296.627	6012391.834	-68.189
2007.00	33 50 46.30629	118 03 32.57448	2256298.27	6012390.33	

References: RS 92-1117

**Description:**

FD PUNCHED BOLT AND WASHER (NO STAMPING), PER LOS ANGELES COUNTY ENGINEER TIES, FIELD BOOK 1536, PAGE 105. LOCATED IN A W'LY DIRECTION FROM THE INTER OF MOODY ST. AND LA PALMA AVE.; SET IN A RAILRD. TIE APPROX. 50' WEST OF THE COYOTE CREEK CHANNEL FLOOD CONTROL ACCESS DR., ACROSS THE RAILRD. TRACKS.

