

GPS #: R122

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 737/G-6

City / Location: Buena Park

Scale Factor: 0.99999958

Ellipsoid Red. Factor: 1.00000250

Combination Factor: 1.00000200

Convergence Angle: -00 58 04.63458

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 51.05127	118 00 41.26137	2268659.013	6027050.658	-51.040
2007.00	33 52 51.06701	118 00 41.27900	2268660.63	6027049.20	

References: RS 92-1117

Description:

FD 2 1/4" LOS ANGELES COUNTY ENGINEER BRASS DISK IN LOS ANGELES COUNTY WELL MONUMENT, DOWN 2.5', STAMPED "LA CO. STA 27 OR. CO." LOCATED NORTH FROM THE INTER OF ARTESIA BLVD. AND KNOTT AVE.; APPROX. 10' SOUTH OF RAILRD. TRACKS, IN A WELL MONUMENT ON KNOTT AVE.

