

GPS #: **R124**

Date Destroyed:

Date Revised: 9/28/2004

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 737/H-5

City / Location: Buena Park

Scale Factor: 1.00000080

Ellipsoid Red. Factor: 1.00000000

Combination Factor: 1.00000080

Convergence Angle: -00 57 47.59454

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

No PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 17.36055	118 00 10.25228	2271274.090	6029709.419	0.075
2007.00	33 53 17.37652	118 00 10.26992	2271275.73	6029707.96	

References: RS 92-1117

Description:

FD 6" CONC. POST WITH 5" DIA. IRON CAP WITH RAISED "29" AND BORDER, SET IN OCS WELL MONUMENT, DOWN 1.5'. LOCATED AT THE APPARENT CENTERLINE INTER OF ALONDRA AVE. AND OCASO AVE.

