

GPS #: **R126**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 737/J-4

City / Location: La Mirada, Los Angeles Co.

Scale Factor: 1.00000200

Ellipsoid Red. Factor: 0.99999919

Combination Factor: 1.00000120

Convergence Angle: -00 57 30.31471

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 43.65815	117 59 38.80683	2273887.601	6032404.503	18.281
2007.00	33 53 43.67431	117 59 38.82463	2273889.26	6032403.03	

References: RS 92-1117

Description:

FD 6" DIA. CONC. POST WITH 5" DIA. IRON CAP WITH RAISED "31" AND BORDER, IN OCS WELL MONUMENT, DOWN 1.5', PER OCS A/3-11, PAGE 140. LOCATED IN THE SEERN PORTION OF THE INTER OF STANTON AVE. AND ASHGROVE DR.

