

GPS #: **R127**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 738/A-4

City / Location: Buena Park

Scale Factor: 1.00000200

Ellipsoid Red. Factor: 0.99999785

Combination Factor: 0.99999991

Convergence Angle: -00 57 12.93870

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 43.84440	117 59 07.18635	2273861.952	6035069.968	46.174
2007.00	33 53 43.86055	117 59 07.20410	2273863.61	6035068.50	

References: RS 92-1117

Description:

FD 3 1/2" OCS ALUMINUM DISK EPOXIED NEAR CENTER OF S'LY SIDEWALK, FLUSH, STAMPED "COUNTY CORNER NO. 32 RESET". LOCATED SE OF THE INTER OF BEACH BLVD. AND ROSECRANS AVE.; SET IN THE SIDEWALK ON THE SOUTH SIDE OF ROSECRANS.

