

GPS #: **R133**

Date Destroyed: **7/26/2000**

Date Revised:

Benchmark Designation:

OCS Index Map: **3L**

Page/Grid: **708/F-4**

City / Location: **La Habra**

Scale Factor: **1.00001100**

Ellipsoid Red. Factor: **0.99998237**

Combination Factor: **0.99999346**

Convergence Angle: **-00 55 46.94852**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 45.88392	117 56 30.70332	2292044.692	6048557.871	369.806
2007.00	33 56 45.90008	117 56 30.72074	2292046.35	6048556.43	

References: **RS 92-1117**

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD WELL MONUMENT WITH PIPE AND 1 1/4" BRASS ORANGE COUNTY SURVEYOR TAG, RE 7872, DOWN 1.0'. LOCATED NORTH OF THE INTER OF WHITTIER BLVD. AND CYPRESS; ON THE APPARENT CENTERLINE OF CYPRESS 0.5 MILE FROM SAID INTER.