

GPS #: **R143**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 709/H-3

City / Location: Unin., Orange County

Scale Factor: 1.00001120

Ellipsoid Red. Factor: 0.99997540

Combination Factor: 0.99998663

Convergence Angle: -00 52 31.98002

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 48.68835	117 50 35.90393	2291857.272	6078449.733	515.612
2007.00	33 56 48.70522	117 50 35.92078	2291859.00	6078448.34	

References: RS 92-1117

Description:

FD 2" I.P. WITH BRASS CAP STAMPED "R9W, T2S, SEC. 32, 1/4, 1/4, SEC. 5, T3S, R9W", UP 1.1'. 6' TALL WITNESS PIPE, 6' SOUTH WITH LA COUNTY BOUNDARY SIGN 2' NORTH AND PADDLE POST 3' NORTH. LOCATED IN A NE'LY DIRECTION OF THE INTER OF THE 57 FREEWAY AND TONNER CANYON RD.; SET INSIDE THE FIRESTONE BOY SCOUT RESERVATION, APPROX. 280' NE ALONG A FENCELINE FROM GATE.

