

GPS #: **R144**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 709/J-3

City / Location: Unin., Orange County

Scale Factor: 1.00001120

Ellipsoid Red. Factor: 0.99996561

Combination Factor: 0.99997683

Convergence Angle: -00 52 15.67408

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 48.47344	117 50 06.23073	2291797.449	6080949.006	720.140
2007.00	33 56 48.49005	117 50 06.24761	2291799.15	6080947.61	

References: RS 92-1117

Description:

FD 2" I.P. WITH BRASS CAP STAMPED "LA CO., T2S, R9W, 32, 33, 5, 4, T3S, R9W O.CO.", UP 1.0'. WITNESS PADDLE 3' NORTH AND WITNESS POST 5' NORTH. LOCATED IN A NE'LY DIRECTION FROM THE INTER OF 57 FREEWAY AND TONNER CANYON RD.; SET INSIDE THE FIRESTONE BOY SCOUT RESERVATION, SET APPROX. 1200' SE ALONG A RIDGE SE FROM THE LOS ANGELES TIMES TRAINING CENTER.

