

GPS #: **R146**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 710/B-3

City / Location: Unin., Orange County

Scale Factor: 1.00001120

Ellipsoid Red. Factor: 0.99994841

Combination Factor: 0.99995963

Convergence Angle: -00 51 40.90790

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 48.42423	117 49 02.96400	2291711.898	6086278.391	1079.614
2007.00	33 56 48.44085	117 49 02.98082	2291713.60	6086277.00	

References: RS 92-1117

Description:

FD 2" I.P. WITH BRASS CAP STAMPED "LA CO., T2S, R9W, 33, 34, 4, 3, T3S, R9W, O.CO.", UP 1.4'. LOCATED NE OF THE INTER OF VALENCIA AVE. AND LAMBERT RD.; SET ON THE COUNTY LINE APPROX. 800' NE ALONG A RIDGE, FROM THE NE CORNER OF A FENCE AROUND A MICROWAVE STATION.

